BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/11/2012-13 Dated:25-01-2014

APPROVED TENDER SCHEDULE –'B'

Item No: 10

Name of Work:-Providing asphalting and BS slab drains at law college cross roads in Attur, ward no:03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri H S PALAKSHAMURTHY	
				Rate	Rate in Words
1	KSRB 2-1.1:Earthwork in surface excavation in hard soil for levelling and lowering the ground mantsaltuy (other than foundation of buildings, culverts, road drains and tronches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled and after breaking of clods and neatly dressed as per specification Specification	Cum	380.16	178.00	Rupees one hundred seventy eight only
2	KSRRB 300-1:Earthwork excavtion by manual means in ordinary soil involving an average horizontal throw upto 2 Meters and an average lift upto 0.5m excavated surface leveled and sides neatly dressed the disposed earth to be levelled neatly after breaking of clods complete as per specificabons and complete as per specifications with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	69.12	65.00	Rupees sixty five only
3	Providing 7.5 cm thick granite slabs of selected quality roughly drossed and fixed in cement mortar (1:6) including fixing curing etc., complete.	Sqm	950.40	350.00	Rupees three hundred fifty only
4	KSRRB M400-17.Providing, laying, spreading and compacting graded stones aggregate to Wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specification. MORTH Specification with all lead and lift etc complete as per specification and direction of engineer incharge of the work	Cum	190.08	1140.00	Rupees one thousand one hundred forty nine only
5	KSRRB M500-6:Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 Kg/sqm using maechanical means complete as per specifications. Morth Specification.	Sqm	1267.20	45.00	Rupees forty five only
6	KSRRB 500-10 Tack coat:Providing and applying tack coat with bitumen emulsion pressure distributor at the rate of 0.20 Kg per sqm on the prepared bitu minous/granular surface cleaned with mechanical broom, complete as per specifications. MORTH Specification No.503 using bitumen emulsion	Sqm	1267.20	12.00	Rupees twelve only

LC 31786

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri H S PALAKSHAMURTHY	
				Rate	Rate in Words
7	KSRRB M 500-18 Providing and laying semi dense bituminous concrete with 100-120 TPH batch type HMP producing an avergae output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bitumious binder at 4.5 to 5% of mix and filler, transporting the hot mix work site, laying with a hydrostatic paver finisher with sensor control to the required grade, levele and alignment,rolling with smooth sheeled, vibratory and tendem rollers to achieve the desired compaction as per MORTH specification clause No 500.8 complete in all respects as per specification 25-30 mm compacted thickness with 5% bitumen 60-70 grade using 40-60 HMP (grading-II)	Cum	31.68	10000.00	Rupees ten thousand only
8	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/sand/.kanker/moorum. KSRRB M100-1:Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH Chapter 1	Cum	425.00	78.00	Rupees seventy eighty only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.